

2025 Meridian Local Roads Program

Job No. MD24001

LOCATION: Tihart Rd, Newman Rd, Tacoma Blvd, Various Tacoma Hills Subdivision Streets

DESCRIPTION: 3.5 miles of HMA base crushing and shaping, Asphalt Base Stabilization, HMA resurfacing, aggregate shoulders, HMA and concrete approaches, drainage improvements, ditch cleanout, sidewalk grading, and slope restoration.

PAY CODE	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	ITEM COST
1027051	_Audio-Visual Recording	LSUM	1		
1100001	Mobilization, Max \$240,000.00	LSUM	1		
2010001	Clearing	Acre	0.22		
2020002	Tree, Rem, 19 inch to 36 inch	Ea	17		
2020003	Tree, Rem, 37 inch or Larger	Ea	11		
2020004	Tree, Rem, 6 inch to 18 inch	Ea	9		
2020006	Stump, Rem, 19 inch to 36 inch	Ea	1		
2030001	Culv, Rem, Less than 24 Inch	Ea	49		
2030005	Culv, End, Rem, Less than 24 inch	Ea	2		
2040020	Curb and Gutter, Rem	Ft	282		
2040050	Pavt, Rem	Syd	666		
2040055	Sidewalk, Rem	Syd	82		
2050006	Ditch Cleanout	Sta	94		
2050010	Embankment, CIP	Cyd	1406		
2050016	Excavation, Earth	Cyd	1622		
2050030	Machine Grading	Sta	367		
2057001	_Sidewalk, Grading	Ft	672		
2080020	Erosion Control, Inlet Protection, Fabric Drop	Ea	35		
2080026	Erosion Control, Maintenance, Sediment Rem	Cyd	50		
2080036	Erosion Control, Silt Fence	Ft	600		
2087001	_Erosion Control, Straw Wattle, 9 Inch	Ft	250		
3027011	_Aggregate Base, Recycled, 4 inch	Syd	510		
3050002	HMA Base Crushing and Shaping	Syd	10556		
3050010	Material, Surplus and Unsuitable, Rem, LM	Cyd	500		
3057011	_Asphalt Stabilized Base, Pre-Processing	Syd	45134		
3057011	_Asphalt Stabilized Base	Syd	40219		
3057012	_Stabilization Asphalt, Engineered Emulsion	Ton	283		
3060021	Maintenance Gravel, LM	Cyd	300		
3070046	Approach, CI III, 4 inch	Syd	1426		
3070048	Approach, CI III, 6 inch	Syd	318		
3070145	Shld, CI III, 3 inch	Syd	6334		
3070146	Shld, CI III, 4 inch	Syd	2037		
4010094	Culv End Sect, Metal, 12 inch	Ea	10		
4010199	Culv, CI A, CSP, 12 inch	Ft	270		
4010607	Culv, CI F, 12 inch	Ft	1471		
4017001	_Culv, Cleanout, Spec	Ft	315		
4030006	Dr Structure Cover, Adj, Case 2	Ea	29		
4030280	Dr Structure, Adj, Add Depth	Ft	22		

2025 Meridian Local Roads Program

4030390	Dr Structure, Temp Lowering	Ea	20		
4037050	_Dr Structure Cover, Adj, Case 1, Modified	Ea	15		
4040061	Underdrain, Subbase, 4 inch	Ft	150		
4040091	Underdrain Outlet, 4 inch	Ft	43		
4040111	Underdrain, Outlet Ending, 4 inch	Ea	1		
5010005	HMA Surface, Rem	Syd	2121		
5010008	Pavt for Butt Joints, Rem	Syd	804		
5010025	Hand Patching	Ton	104		
5010033	HMA, 13A	Ton	5781		
5010034	HMA, 36A	Ton	1621		
5010061	HMA Approach	Ton	681		
5017031	_HMA Additive, RTR Modified, PG 46 -34	Ton	3393		
5017031	_HMA Additive, RTR Modified, PG 52 -28	Ton	4009		
6030005	Cement	Ton	60		
8010005	Driveway, Nonreinf Conc, 6 inch	Syd	666		
8020016	Curb and Gutter, Conc, Det B2	Ft	348		
8020038	Curb and Gutter, Conc, Det F4	Ft	200		
8030030	Curb Ramp Opening, Conc	Ft	60		
8050010	Curb Slp, HMA	Ft	2219		
8070095	Post, Mailbox	Ea	100		
8087001	_Fence, Ornamental Aluminum, 48 inch	Ft	50		
8127051	_Temporary Traffic Control Devices	LSUM	1		
8167011	_Slope Restoration, Type II	Syd	19235		
8167011	_Slope Restoration, Type IV	Syd	5000		
8167011	_Slope Restoration, Type VI	Syd	15138		
8167011	_Slope Restoration, Type VII	Syd	500		
8210001	Monument Box	Ea	3		
8210010	Monument Preservation	Ea	3		
8230431	Gate Box, Adj, Case 1	Ea	1		
8252144	Sanitary Structure, Adj, Add Depth	Ft	5		
8252146	Sanitary Structure Cover, Adj, Case 2	Ea	6		
8257010	_Sanitary Structure, Chimney Seal, External	Sft	180		
8257050	_Sanitary Structure Cover	Ea	4		
8257050	_Sanitary Structure Cover, Adj, Case 1, Modified	Ea	6		
Project Total:				\$	-

Contractor

Signature

Date

(Printed Name, Title)